

Zestawienie robót w zakresie wykonania odwodnienia i rowów

		pobocze umocnione mat.kamiennym			renowacja rowów	umocnieni e dna rowu	umocnienie skarp płyty ECO 40x60	umocnieni e skarp płyty 50x50x7
	strona prawa	dł.	szer	pow.				
		m	m	m2	mb	mb	m2	
od km	do km							
0+400	0+500	100,0	0,75	75,0	10,0			
0+500	0+600	80,0	0,75	60,0	75,0			
0+600	0+700	75,0	0,75	56,3	75,0			
0+700	0+800	85,0	0,75	63,8	85,0			
0+800	0+900	80,0	0,75	60,0	80,0			
0+900	1+000	85,0	0,75	63,8	85,0			
1+000	1+100	80,0	0,75	60,0	80,0			
1+100	1+200	80,0	0,75	60,0	80,0			
1+200	1+300	80,0	0,75	60,0	80,0			
1+300	1+400	90,0	0,75	67,5	90,0			
1+400	1+513,93	113,0	0,75	84,8	110,0			
		948,0		711,2	850,0	0,00	0,00	0,00