

Zestawienie robót w zakresie wykonania odwodnienia i rowów

		pobocze umocnione mat.kamiennym			renowacja rowów	umocnienie dna rowu	umocnienie skarp płyty ECO 40x60	umocnieni e skarp płyty 50x50x7
strona prawa		dł.	szer	pow.				
		m	m	m2	mb	mb	m2	
od km	do km							
0+000	0+100	100,0	0,75	75,0	100,0			
0+100	0+200	95,0	0,75	71,3	95,0			
0+200	0+300	90,0	0,75	67,5	90,0			
0+300	0+400	100,0	0,75	75,0	100,0			
0+400	0+500	90,0	0,75	67,5	90,0			
0+500	0+600	100,0	0,75	75,0	100,0			
0+600	0+700	95,0	0,75	71,3	95,0			
0+700	0+800	85,0	0,75	63,8	85,0			
0+800	0+900	85,0	0,75	63,8	85,0			
0+900	1+000	90,0	0,75	67,5	90,0			
1+000	1+100	95,0	0,75	71,3	100,0			
1+100	1+200	90,0	0,75	67,5	90,0			
1+200	1+300	85,0	0,75	63,8	85,0			
1+300	1+400	90,0	0,75	67,5	90,0			
1+400	1+500	95,0	0,75	71,3	95,0			
1+500	1+600	90,0	0,75	67,5	90,0			
1+600	1+700	100,0	0,75	75,0	100,0			
1+700	1+800	90,0	0,75	67,5	90,0			
1+800	1+900	95,0	0,75	71,3	95,0			
1+900	2+000	85,0	0,75	63,8	85,0			
2+000	2+100	88,0	0,75	66,0	88,0			
2+100	2+200	92,0	0,75	69,0	92,0			
2+200	2+300	90,0	0,75	67,5	90,0	45,0	90,0	
2+300	2+400	100,0	0,75	75,0	100,0	95,0	190,0	
2+400	2+500	90,0	0,75	67,5	90,0	67,0	134,0	
2+500	2+600	90,0	0,75	67,5	90,0			
2+600	2+700	100,0	0,75	75,0	100,0			
2+700	2+800	90,0	0,75	67,5	65,0			
2+800	2+900	95,0	0,75	71,3				
2+900	3+000	95,0	0,75	71,3				
3+000	3+100	100,0	0,75	75,0				
3+100	3+200	100,0	0,75	75,0				
3+200	3+300	100,0	0,75	75,0				
3+300	3+400	95,0	0,75	71,3				
3+400	3+500	90,0	0,75	67,5				
3+500	3+600	85,0	0,75	63,8				
3+600	3+645,1	40,0	0,75	30,0				
		3385,0		2539,4	2 565,0	207,00	414,00	0,00

m³ 203,15