

Zestawienie robót w zakresie wykonania odwodnienia i rowów

		pobocze umocnione mat.kamiennym			renowacja rowów	umocnieni e dna rowu	umocnienie skarp płyty ECO 40x60	umocnienie skarp płyty 50x50x7
strona lewa		dł.	szer	pow.				
		m	m	m2	mb	mb	m2	
od km	do km							
0+000	0+100	100,0	0,75	75,0				
0+100	0+200	95,0	0,75	71,3				
0+200	0+300	100,0	0,75	75,0	50,0			
0+300	0+400	95,0	0,75	71,3	95,0			
0+400	0+500	90,0	0,75	67,5	90,0			
0+500	0+600	85,0	0,75	63,8	85,0			
0+600	0+700	83,0	0,75	62,3	83,0			
0+700	0+800	77,0	0,75	57,8	77,0			
0+800	0+900	80,0	0,75	60,0	80,0			
0+900	1+000	90,0	0,75	67,5	90,0			
1+000	1+100	95,0	0,75	71,3	100,0			
1+100	1+200	95,0	0,75	71,3	95,0			
1+200	1+300	95,0	0,75	71,3	100,0			
1+300	1+400	90,0	0,75	67,5	90,0			
1+400	1+500	100,0	0,75	75,0	100,0			
1+500	1+600	95,0	0,75	71,3	95,0			
1+600	1+700	95,0	0,75	71,3	95,0			
1+700	1+800	90,0	0,75	67,5	90,0			
1+800	1+900	88,0	0,75	66,0	88,0			
1+900	2+000	87,0	0,75	65,3	87,0			
2+000	2+100	85,0	0,75	63,8	100,0			
2+100	2+200	95,0	0,75	71,3	95,0	20,0	40,0	
2+200	2+300	85,0	0,75	63,8	85,0	90,0	180,0	
2+300	2+400	95,0	0,75	71,3	95,0	100,0	200,0	
2+400	2+500	90,0	0,75	67,5	90,0	90,0	180,0	
2+500	2+600	100,0	0,75	75,0	100,0			
2+600	2+700	100,0	0,75	75,0	100,0			
2+700	2+800	80,0	0,75	60,0	80,0			
2+800	2+900	95,0	0,75	71,3	95,0			
2+900	3+000	100,0	0,75	75,0	100,0			
3+000	3+100	95,0	0,75	71,3	95,0			
3+100	3+200	95,0	0,75	71,3	95,0			
3+200	3+300	90,0	0,75	67,5	90,0			
3+300	3+400	95,0	0,75	71,3	95,0			
3+400	3+500	100,0	0,75	75,0	100,0			
3+500	3+600	95,0	0,75	71,3	95,0			
3+600	3+645,1	45,0	0,75	33,8	40,0			
		3365,0		2524,8	3 140,0	300,00	600,00	0,00

m³ 201,98